

TOWN OF BARRE

5-YEAR GRAVEL ROAD PLAN

F.Y.
2013 - 2017

Approved By Selectboard: November 1, 2011

YEAR 1: 2012-2013

Road Section

Type of Work

West Road (entire)

Remove 6"-8", consider recycled asphalt

Cheney Road (entire)

Reconstruct (fabric)

Beckley Hill Road (EOP to LePage)

Remove and replace 4"-6" gravel; ditch and stoneline as needed; road base drainage just above LePage Rd.

Lyman Road (entire length)

Ditch as needed, stone-line ditches where needed, reconstruct road

TOP DRESSING

Cutler/Taplin area*

Any road or section of road reconstructed (listed as a project) in the 2 previous years, or any road or section of road scheduled for a project in the next 2 years will not be top dressed this year.

**See attached list of roads in this area*

YEAR 2: 2013-2014

<u>Road Section</u>	<u>Type of Work</u>
Lowery Road (Donahue Rd. to Fournier's) and (past Johnson's)	Add 4" gravel Ditching
Upper Usle Road (entire)	Ditch, reconstruct entire; use fabric from Smith farmhouse to L. Usle
Averill Road (entire)	Topdress 4"-6"
Littlejohn Road	150' section by quarry - deep reconstruction

TOP DRESSING

West Hill*

Any road or section of road reconstructed (listed as a project) in the 2 previous years, or any road or section of road scheduled for a project in the next 2 years will not be top dressed this year.

**See attached list of roads in this area*

YEAR 3: 2014-2015

Road Section

Type of Work

Spruce Mountain View (entire)

6" removal and replacement

Belding Road (entire length)

Add 4"-6" new gravel.

Taplin Road (E. Cobble Hill Rd. to Grout's)

Add 4"-6" new gravel.

Clark Road (Swift Rd. to mid-point)

Ditch, 4"-6" topdress; guardrail needed

Miller Woods Road

Topdress 4"-6" gravel

TOP DRESSING

Beckley - Richardson area*

Any road or section of road reconstructed (listed as a project) in the 2 previous years, or any road or section of road scheduled for a project in the next 2 years will not be top dressed this year.

**See attached list of roads in this area*

YEAR 4: 2015-2016

Road Section

Type of Work

Old Route 302 (entire length, 2100')

Remove some top gravel;
replace with 4"-6" new
gravel.

Neddo Road (entire length, 1850')

Top dress with 4"-6" gravel.

Swift Road (Morgan Ln. to Mitchell Rd.)

Reconstruct using fabric.

Lower Usle Road

Remove and replace 6" top
gravel.

(Lower) Phelps (Osborne Rd. to Lamberti's house)

Reconstruct

TOP DRESSING

East Hill area*

Any road or section of road reconstructed (listed as a project) in the 2 previous years, or any road or section of road scheduled for a project in the next 2 years will not be top dressed this year.

**See attached list of roads in this area*

YEAR 5: 2016-2017

Road Section

Type of Work

LePage Road (Beckley Hill Rd. to Ladd Farm)

Topdress 3"-4" with crushed gravel; check ditching

Jensen Road

Topdress 4"-6" gravel

Mitchell Nursery Road

Remove, replace gravel where needed; topdress 4"-6"

TOP DRESSING

East and South Barre areas*

Any road or section of road reconstructed (listed as a project) in the 2 previous years, or any road or section of road scheduled for a project in the next 2 years will not be top dressed this year.

**See attached list of roads in this area*